Chuck Votpka

217 West 2nd Street Washington, KS 66968 785.541.0924

ESTIMATE

93 FT. Basement Repair

\$13,020.00

Dig out along outside of wall to footing, use tacks to push out walls as close to original as possible.

Cut vertical slots in block on outside of wall every 4 feet. Chip out cell and install ¾" rebar. Pour cells with cement.

Wire Wheel and clean entire surface plaster with structural bonding cement (Shurwall). Coat with Grey Shield (rubber membrane coating) install new drain tile cover with gravel back fill.

22 FT. New Footing

\$4,400.00

Dig out and remove existing footing. Pour new footing and lay block back with grout cell every 3 feet and 1 horizontal beam block plaster outside and coat with grey shield and back fill.

Total \$17,420.00

Chuck Votipka - Owner